



SUPERCAP®

The Next Generation Slab™

PROJECT SNAPSHOT



As Shady Grove Hospital prepared to perform major renovations to a new wing of its medical center, a severe deflection in the underlying concrete slab was noticed. FF numbers were critical since a large part of the renovation was a neonatal unit and the specifications were extremely tight.

East Coast Poured Floors, Inc. was called in to survey and ensure that the day-to-day functions of the hospital would not be interrupted during installation. Utilizing the LATICRETE® SUPERCAP® System, nothing but a hose and five men entered the building throughout that entire time.



East Coast poured an average depth of 2.25 inches to fill this deflection and hit the specification with LATICRETE SUPERCAP FAST, without interrupting any hospital functions whatsoever.

LOCATION
Rockville, MD

GENERAL CONTRACTOR
Whiting-Turner
Baltimore, MD

INSTALLER
East Coast Poured Floors, INC
Balitmore, MD

FEATURES
5,000 Square Feet
2.25" Average Depth

NEONATAL UNIT, SHADY GROVE HOSPITAL, MD